



TREATMENT 1 - to tree planting




D 04 Topsoil depths to planted areas
Scale @ 1:25

TREATMENT 2 - to shrub planting areas





TREATMENT 3 - to grass planting areas



* NOTE: All topsoil to be inspected and approved by Landscape Architect prior to spreading / backfilling

D 07 Reroot 2000, root barrier supplied by Greenleaf Ireland or equivalent, 1500mm depth, 2.0mm thick



ReRoot 2000

Deep application root barrier



ReRoot 2000 was specified and installed at the industrial park at Spire, Liverpool. Note how trees have been planted parallel to a major gas main with this approval of Transco.


Benefits

- Resistant to puncture by sharp objects or tearing as a result of soil movement
- Durable, resistant to biodegradation and photodegradation
- Easy to install, no specialist equipment needed
- Available in standard 0.3m, 0.6m, 1.0m, 1.5m and 2.0m depth rolls, up to 6 metre deep rolls to special order
- Supplied in roll form to any 10 km increment
- Available in 1.0mm (product code RER110), and 2.0mm thickness (product code RER200)
- Effective in the control of Japanese Knotweed and other invasive plants
- ReRoot 2000 fulfils all the Arboricultural Advisory and Information Service guidelines for root barriers
- Manufactured from 100% recycled material

ReRoot 2000 is a high strength root barrier for deeper applications. This product has been used extensively on many projects around the UK, particularly in new service infrastructure projects, business parks and housing developments.

ReRoot 2000 is rigid enough to hold its form when placed into a trench. This is a big advantage as it will not be dragged downward during backfilling. Market leading puncture resistance and strength, mean that this is the root barrier of choice for specifiers and utility companies requiring root free service corridors.

The high puncture resistance of ReRoot 2000 allows easier compaction close to the barrier ensuring an excellent product/soil interface.



ReRoot 2000 can be used to keep tree roots from damaging services and paved areas



ReRoot 2000 related to protect hard surfaces at Quorn, Leicestershire

ReRoot 2000 will hold its form in a trench excavation. This makes installation quick and easy. Also, visible is land drain to remove groundwater pressure

ReRoot 2000 has been installed prior to topsoiling in this infrastructure project

Product specification and codes			
Product	Thickness	Depth	Code
ReRoot 2000	1.0mm	300mm	RER1030.3A
ReRoot 2000	1.0mm	600mm	RER1030.6A
ReRoot 2000	1.0mm	1000mm	RER1031.0A
ReRoot 2000	1.0mm	1500mm	RER1031.5A
ReRoot 2000	2.0mm	1000mm	RER2031.0A
ReRoot 2000	2.0mm	1500mm	RER2031.5A
ReRoot 2000	2.0mm	2000mm	RER2032.0A
ReRoot joint tape (10m roll)	-	-	REFUTA

Typical installation specification

Install ReRoot 2000 (including relevant product code) linear root barrier as follows:
Excavate narrow trench between the tree and the structure to be protected. Please note: the positioning of the trench will depend on tree species and other site conditions. Please consult a qualified arboriculturist.

The barrier should be positioned in the trench against the side of the trench nearest the tree. Any sharp objects should be removed from the trench walls and the backfill material.
ReRoot 2000 roll ends can be joined by overlapping at least 500mm and securing both sides with Greenleaf root barrier joining tape. For critical applications the material can be seam welded.

Ensure that the top of the barrier finishes at least 10mm above finished soil levels, tree side, to avoid subsequent root over growth. The barrier can be trimmed using a sharp knife. Backfill the trench in layers, compacting carefully.

It may be desirable, depending on site conditions, to encapsulate the top edge of the barrier in concrete banding to protect the barrier and to finish the installation tidily.

Greenleaf

Sales and service: 01424 717707
Technical assistance: 01424 432033
Sales Fax line: 01424 533003
Email: enquiries@greenleafrees.co.uk
Website: greenleafrees.co.uk

Rev.	Date	Note
00	0000-00-00	00



Registered
Landscape
Architect

General Notes

Doyle &
O'Troithigh
Landscape
Architecture

Project Name
Mixed Use Development - Arklow

Status
Planning

Project No
26-008

Scale
Scale 1:25

Date
23/09/2026

Linda Doyle
Director
+353 (0)87 267 4196
linda@doyle-o'troithigh.com

Dalí O'Troithigh
Director
+353 (0)86 300 3469
dalio@doyle-o'troithigh.com

Drawing Name
Landscape Details 04

Drawing No
LD-04-PP

Revision No
00

Drawn By
D.C.

Checked By
D&OT

Office Address
13 Adelaide Road,
Dublin 2

Contact
mail@doyle-o'troithigh.com
+353 (0)1 539 2737